

15.145.20754.0000

337 R

To: 1 030653
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,754
C NE SE, SEC. 21, T 20 S, R 19

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

1980 feet from S section line
660 feet from E section line
Lease Name Thurman Well # 1

Operator: Sunburst Exploration Company, Inc.
Name & Address: 112 Corporate Place
125 N. Emporia
Wichita, KS 67202

County Pawnee 150.68
Well Total Depth 4305 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 506

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 28 Month: January Year: 19 86

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4299' Perfs at 4265-4267 and Open Hole from 4299-4305

1st plug sand back to 4210' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 pm Day: 28 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4210' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1986

Maximum pressure 800 psi and shut in 200 psi

CONSERVATION DIVISION 2-4-86

Remarks: Recovered 2400' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE FEB 6 1986

INV. NO. 12418