

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24126-00-00
Spot: NWNESE Sec/Twnshp/Rge: 23-20S-21W
2310 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MCJUNKIN A Well Number: 1
County: NESS Total Vertical Depth: 4392 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 216
Production: Size feet:
Liner: Size feet:

11/2
142.74

Well Type: DH UIC Docket No: Date/Time to Plug: 01/02/2001 2:30 AM

Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.

Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 220' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 01/02/2001 4:30 AM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 220' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 05 2001

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE

1/8/01

JAN 02 2001

WV. NO.

2001061245

Form CP-2/3

MP