

6-100496

10-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,585.0000

SE NE SW NW/4 SEC 30, 20 S, 11 W
1825 feet from N section line
1075 feet from W section line

Operator license# 31535

Lease: SOEKEN Well # 1

Operator: Petroleum Resources LTD.

County: BARTON

Address: P.O. Box 467

Well total depth: 3480 feet

Newkirk, OK

Conductor pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 265 feet

74647

Abandoned Oil well: Gas Well: Input Well: SWD Well: D & A: X

Plugging contractor: DUKE DRILLING COMPANY License: 05929

Address:

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: JOHN ARMBRUSTER

Company: DUKE DRILLING COMPANY Phone:

Were: Spot all plugs through drill with heavy mud between all plugs.

1st plug @ 3400 feet with 25 sacks

Rat hole: 15 sacks

2nd plug @ 590 feet with 25 sacks

Mouse hole: 10 sacks

3rd plug @ 300 feet with 75 sacks

Wiper plug @ 40 feet

4th plug @ 40 feet with 10 sacks

5th plug @ feet with sacks

Plugging proposal received by: DAVID WANN

Plugging operations attended by agent? All[], Part[], None[X]

Completed: hour: 11:20 PM, Day: 19, Month: October, Year: 1994

Actual plugging report: Hole reported plugged as above

Order 160 sx 60/40 posmix w/ 6% gel and 0 sx celloflake or flowcel.

Remarks: Elevation: 1814 G Anhydrite depth: 587 feet, Anhy. plug: T
Dakota plugged: T Bottom hole plug in place (A/E/N): A
Plugged through drill pipe: T
Arbuckle: 3382 Cemented by: HALLIBURTON

INVOICED I did not [X] observe the plugging.

Signature: (TECHNICIAN) 11-16-94

DATE 11-18-94

INV. NO. 41713 10-19 FEB 16 1995