

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-00017-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 30-25S-41W
3031 feet from S Section Line, 2300 feet from E Section Line
Lease Name: GOULD Well #: 1
County: HAMILTON Total Vertical Depth: 6453 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5065		WITH 2 SX CMT
PROD	5.5	5225	0	WITH 165 SX CMT
SURF	10.75	323		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2018 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOSE REYES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2018 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5065' WITH 2 SX CMT. LOAD HOLE WITH WATER & RUN CBL FROM 5050' TO 0'. APPARENT TOC @ 2950'. PERFORATE 4 HOLES AT 2010'. RUN TBG & PACKER TO 1620'. INJECTION RATE 3 BPM AT 500#. PUMP 50 SX CMT WITH 25# HULLS IN THE LAST 25 SX CMT. DISPLACE CMT LEAVING 25 SX CMT INSIDE THE CASING & 25 SX CMT OUTSIDE THE CASING. HOLDING 200 PSI. PERFORATE 4 HOLES AT 650'. INJECTION RATE 4 BPM @ 200#. NO BLOW UP ANNULUS. PUMP 80 SX CMT WITH 50# HULLS DOWN 5 1/2". STAYED FULL. PUMP 40 SX CMT DOWN THE ANNULUS. CASING WENT ON VACUUM. PUMP ADDITIONAL 130 SX CMT WITH 125# HULLS DOWN THE 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
5142	5144		
5120	5128		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
TR

(TECHNICIAN)

RECEIVED
APR 24 2018
KCC DODGE CITY