

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21600-00-00
Spot: SESWNWNE Sec/Twship/Rge: 30-22S-23W
4016 feet from S Section Line, 2292 feet from E Section Line
Lease Name: SCOTTY-LLOYD Well #: 1-30
County: HODGEMAN Total Vertical Depth: 4670 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1587		CEMENTED WITH 150 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	5.5	4669	0	WITH 170 SX CMT
SURF	8.625	227		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: OCTAVIO MORALES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PUMP 35 SX CMT WITH 100# HULLS AT 4600'. 1650'-0' FULL WITH CMT. PUMP CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2017 12:35 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4599' & PUMPED 35 SX CMT WITH 100# HULLS. PULLED TBG TO 1638' & CIRCULATED CMT TO SURFACE WITH 170 SX CMT. PULLED TBG & TOPPED OFF WITH 25 SX CMT. PRESSURED BACKSIDE TO 200# WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4625	4627		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

MAY 07 2018

Plugged through: TBG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
APR 12 2018
KCC DODGE CITY [Signature]

SA