

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21617-00-00
Spot: SESESWNW Sec/Twnshp/Rge: 30-22S-23W
2783 feet from S Section Line, 4058 feet from E Section Line
Lease Name: RUDZIK-WARNER Well #: 1-30
County: HODGEMAN Total Vertical Depth: 4617 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4575		WITH 2 SX CMT
PC		1592		CEMENTED WITH 175 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	4616	0	WITH 125 SX CMT
SURF	8.625	212		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2018 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOSE REYES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4575' WITH 2 SX CMT. RUN TBG TO 1650' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2018 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4575' WITH 2 SX CMT. RUN TBG TO 1638' & PUMPED 175 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4606	4616		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

INVOICED
MAY 07 2018

Plugged through: CSG

District: 01

RECEIVED
APR 12 2018
KCC DODGE CITY

Signed

Michael Maier
SR

(TECHNICIAN)