

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-24354-00-00  
Spot: SESESWNW Sec/Twnshp/Rge: 7-7S-19W  
2400 feet from N Section Line, 1240 feet from W Section Line  
Lease Name: RIFFEGASPER Well #: 7-1  
County: ROOKS Total Vertical Depth: 3651 feet

Operator License No.: 34151  
Op Name: BRINKER ENTERPRISES, LLC  
Address: 216 S MARSHALL ST  
GLEN ELDER, KS 67446

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	244		185 sx

Well Type: DH UIC Docket No: Date/Time to Plug: 04/10/2018 12:00 AM  
Plug Co. License No.: 35410 Plug Co. Name: STP DRILLING LLC  
Proposal Rcvd. from: KIRBY Company: STP DRILLING LLC Phone: (785) 421-7036

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 04/10/2018 10:00 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3506 w/50 sx  
2nd plug @1625 w/50 sx  
3rd plug @960 w/100 sx  
4th plug @300 w/50 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx

Perfs:

Remarks: SOS

Plugged through: DP

4-30-18  
KCC WICHITA  
APR 30 2018  
RECEIVED

INVOICED  
APR 07 2018

District: 04

Signed Ed Schumacher  
(TECHNICIAN)

APR 28 2018