

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-22551-00-00  
Spot: W2NWNENE Sec/Twnshp/Rge: 15-19S-29W  
4950 feet from S Section Line, 1239 feet from E Section Line  
Lease Name: WILLIAMS-HESS "A" Well #: 1-15  
County: LANE Total Vertical Depth: 4702 feet

Operator License No.: 34579  
Op Name: COBALT ENERGY LLC  
Address: 115 S. BELMONT #12 PO BOX 8037  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4415		WITH 2 SX CMT
PC		2191		CEMENTED TO SURFACE
PROD	4.5	4699	0	WITH 175 SX CMT
SURF	8.625	266		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2018 11:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: DALTON POPP Company: COBALT ENERGY Phone: (620) 786-4442

Proposed Plugging Method: CIBP @ 4400' WITH 2 SX CMT. FILL WITH CMT FROM 2220'-0'. TOP OFF & PRESSURED BACKSIDE WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/01/2018 12:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4415' WITH 2 SX CMT. RAN TBG TO 2210'. CIRCULATE CMT TO SURFACE WITH 150 SX CMT. TOOH & TOP OFF CASING WITH 25 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS. PRESSURE TO 200#.

Perfs:

Top	Bot	Thru	Comments
4446	4450		

INVOICED  
MAY 07 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
5/1/18

(TECHNICIAN)

RECEIVED  
MAY - 3 2018  
KCC DODGE CITY