

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-31702-00-00
Spot: NENWNE Sec/Twnshp/Rge: 27-33S-17E
4767 feet from S Section Line, 1311 feet from E Section Line
Lease Name: HORTON Well #: 1-27
County: MONTGOMERY Total Vertical Depth: 1005 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	986		130 SX
SURF	8.625	250		50 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/29/2018 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHSLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 980' (E-LOG TD), "GEL THE WELL UP" (PMP IN A MIXTURE OF BENTONITE AND WTR W/ SOME COTTON SEED HULLS BLENDED IN) THEN PMP A 180' CMT PLUG ON BTM, PU TBG TO 700' PMP IN A 160' CMT PLUG, PU TBG TO 250' TO SURF, "TOP OFF" PROD CSG, PRESS UP TO 250 PSI, AND SHUT WELL-IN. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOCATION.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 03/29/2018 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 980' gelled hole and spotted 22 sack plug. Pulled up to 700' and spotted 22 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. Hooked onto casing and squeezed another barrel slurry into well. Shut well in with 150 psi on casing. A total of 60 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
878	882		
817	819		
685	687		
615	618		
548	882		

RECEIVED
KCC DIST # 3
MAY 01 2018
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

INVOICED
MAY 07 2018

District: 03

Signed 
(TECHNICIAN)