

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-31374-00-00
Spot: NWSWNE5W Sec/Twnshp/Rge: 33-33S-17E
1825 feet from S Section Line, 3875 feet from E Section Line
Lease Name: PAPE/MULLER Well #: 11-33
County: MONTGOMERY Total Vertical Depth: 960 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	951		100 SX
SURF	8.625	256		125 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/28/2018 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH W/ 2 3/8" TBG TO 946' (E-LOG TD), "GEL THE HOLE UP" (PMP IN A MIXTURE OF BENTONITE AND WATER W/ COTTON SEED HULLS BLENDED IN), THEN PMP IN A 150' CMT PLUG ON BTM, PU TBG TO 700', PMP IN A 100' CMT PLUG (THESE TWO PLUGS WILL COVER ALL PERFS), PU TBG TO 250', PMP IN AND CIRC CMT TO SURF, POOH TBG, "TOP OFF" PROD CSG W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 03/28/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 942' gelled hole and spotted 20 sack plug. Pulled up to 700' and spotted 14 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. Hooked onto casing and squeezed one barrel slurry of cement down casing. Well did not pressure up. Well was shut in. A total of 60 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
950	954		
690	692		
632	635		
616	890		

RECEIVED
KCC DIST # 3
MAY 01 2018
CHANUTE, KS

DS


Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY THE OPERATOR WITH THE KCC.

Plugged through: TBG

INVOICED
MAY 07 2018

District: 03

Signed



(TECHNICIAN)