

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-31827-00-00
Spot: NESESE Sec/Twnshp/Rge: 29-33S-17E
914 feet from S Section Line, 419 feet from E Section Line
Lease Name: STATON Well #: 16-29
County: MONTGOMERY Total Vertical Depth: 1015 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1007		125 SX
SURF	8.625	250		130 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/29/2018 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1005' "GEL THE WELL UP" (PMP IN A MIXTURE OF BENTONITE AND WTR W/ COTTON SEED HULLS BLENDED IN), THEN PMP A 120' CMT PLUG, PU TBG TO 850', PMP IN A 50' CMT PLUG, PU TBG TO 760', PMP IN A 50' CMT PLUG, PU TBG TO 675', PMP IN A 50' CMT PLUG, PU TBG TO 885', PMP IN A 50' CMT PLUG, (THESE PLUGS WILL COVER ALL PERFS), PU TBG TO 250', PMP IN AND CIRC CMT TO SURFACE. (THE SUBJECT WELL HAS 250' OF SURF CSG CMTD TO THE TOP, SO WOULD LIKE TO PU TBG TO 100', PMP IN AND CIRC CMT FROM THIS DEPTH IF OK'D BY DISTRICT 3 OFFICE IN CHANUTE, KS)

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 03/29/2018 3:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1001' gelled hole and spotted 14 sack plug. Pulled up to 850' and spotted 7 sack plug. Pulled up to 760' and spotted 7 sack plug. Pulled up to 585' and spotted 7 sack plug. Pulled up to 200' and circulated cement to surface. Pulled 2" and topped well off. A total of 67 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
902	905		
837	839		
754	756		
656	660		
574	905		

RECEIVED
KCC DIST # 3
MAY 01 2018
CHANUTE, KS

DS

INVOICED

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC MAY 07 2018

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)