

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-31019-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 4-34S-17E
4768 feet from S Section Line, 3222 feet from E Section Line
Lease Name: WISHALL Well #: 3-4
County: MONTGOMERY Total Vertical Depth: 1025 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1013		105 SX
SURF	8.625	42		45 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/28/2018 10:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1010' (E-LOG TD), "GEL THE HOLE UP" (PMP IN A MIXTURE OF BENTONITE AND WTR W/ COTTON SEED HULLS BLENDED IN) HTEN PMP IN A 200' CMT PLUG ON BTM, PU TBG TO 710' PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP CMT TO SURF, POOH TBG, "TOP OFF" PROD CSG, PRESS UP TO 250 PSI, SWI. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 03/28/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1007' gelled hole and spotted 26 sack plug. Pulled up to 710' and spotted 7 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. Hooked onto casing and squeezed 1 barrel cement slurry down casing. Pressured up to 200psi, Shut well in. A total of 59 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
897	900		
834	836		
702	900		

RECEIVED
KCC DIST # 3
MAY 01 2018
CHANUTE, KS

DS


INVOICED
MAY 07 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)