

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19169-00-00  
Spot: NESESENW Sec/Twnshp/Rge: 3-25S-5E  
3270 feet from S Section Line, 2783 feet from E Section Line  
Lease Name: FRANK ROBISON Well #: 36  
County: BUTLER Total Vertical Depth: 2544 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2542		175 SX
SURF	13	126		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/17/2018 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: \_\_\_\_\_ Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/18/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH WITH TUBING @ 2400'. QWS MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS & DISPLACED IN CASING. LAYED DOWN TUBING. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251' (4 HOLES). RIH W/TUBING @ 260'. QWS ESTABLISHED CIRCULATION, MIXED AND PUMPED 340 SXS 60/40 POZMIX 4% GEL 2% CC, CEMENT DID NOT CIRCULATE. 4-19-2018 RIH WITH 1" TUBING ON BACKSIDE @ 126'. QWS MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. RIH WITH 1" TUBING ON INSIDE @ 76', QWS MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
2542	2544	OH	

Remarks: COMPLIANCE LIST/DENIED TA

INVOICED

MAY 07 2018

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)