

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22577-00-00
Spot: W2NESWNE Sec/Twnshp/Rge: 20-28S-4E
3690 feet from S Section Line, 1949 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 6
County: BUTLER Total Vertical Depth: 2490 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2400		
PROD	5.5	2490		100 SX
SURF	8.625	202		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS / 35 SXS @ 2480'. CIRCULATE & PERF @ 255'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/31/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2400'. DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH IN WIRELINE, PERFORATED SQUEEZE HOLES @ 255'-256' (4 HOLES). RIH W/ TUBING @ 270', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 65 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING & SWEDGED INTO CASING. MIXED & PUMPED 170 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS. NO CIRCULATION. WAITED 3 HOURS. DID NOT TAG CEMENT, RIH WITH TUBING @ 270'. QWS ESTABLISHED CIRCULATION AND PUMPED 2 SX CEDAR FIBER, 100# HULLS & 60 SXS 60/40 POZMIX, 4% CC & DISPLACED IN CASING. SDON 1-31-2018. RIH W/ 1" TUBING ON BACKSIDE @ 150', QWS MIXED & PUMPED 65 SXS POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. TOPPED INSIDE WITH 5 SXS.

Perfs:

Top	Bot	Thru	Comments
2482	2484	CSG	

Remarks: COMPLIANCE/ DENIED TA

INVOICED
MAY 07 2018

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)