

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-26816-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 10-32S-11E  
4930 feet from S Section Line, 2245 feet from E Section Line  
Lease Name: HUDSON AB Well #: 10-C1  
County: CHAUTAUQUA Total Vertical Depth: 2114 feet

Operator License No.: 35018  
Op Name: ENTRANSCO ENERGY, LLC  
Address: PO BOX 578  
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2104		135 SX
SURF	8.625	40		12 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2018 10:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: RAY GILBERT Company: \_\_\_\_\_ Phone: (620) 820-9687

Proposed Plugging Method: Plug per KCC regulations

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 04/20/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 2112' gelled hole and spotted 5 sack plug. Pulled up to 1000' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. Washed 1" down backside of production casing to 60' and circulated cement to surface. Pulled 1" and topped off. A total of 60 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
APR 27 2018  
CHANUTE, KS

DS


INVOICED  
MAY 08 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)