

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-111-20064-00-00
Spot: SWSWSE Sec/Twnshp/Rgc: 16-16S-10E
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KIZLER Well #: 3
County: LYON Total Vertical Depth: 3280 feet

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL ST PO BOX 577
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3279		100 SX
SURF	8.625	210		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2018 12:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: J C HAWES Company: _____ Phone: (620) 342-1148

Proposed Plugging Method: Spot sand and cement plug at 3200 ft., Circ hole clean, spotted 25 sx plug at 1699, pull up to 260 ft., circ cement to surface, RIH between 4.500" casing and 8.625" surface w/ 1" to 260 ft., circ cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 04/16/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 3210', pumped 25 sxs cement, pulled tubing to 1520', pumped 15 sxs cement, pulled tubing to 260' pumped 25 sxs cement, ran 1" to 135' o backside of casing pumped 70 sxs cement, circ. Cement to surface,

Perfs:

Top	Bot	Thru	Comments
3220	3223		

RECEIVED
KCC DIST # 3
APR 23 2018
CHANUTE, KS
MH
INVOICED
MAY 08 2018

Remarks: !

Plugged through: TBG

District: 03

Signed Mico Heffern
(TECHNICIAN)

810 E 7th
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 3856
 Foreman Russell McLoy
 Camp Eureka

APR-11-20064-00-00

Date	Cust. ID#	Lease & Well Number	Section	Township	Range	County	State
4-16-18	1001	Kizler #3	16	16S	10E	LYON	KS
Customer Glacier Petroleum INC.			Unit #	Driver		Unit #	Driver
Mailing Address P.O. Box 577			104	ALAN M			
City Emporia			113	AB			
State KS							
Zip Code 66801							

Job Type P.T.A. Hole Depth _____ Slurry Vol. _____ Tubing 1" + 2 3/8
 Casing Depth 3279 Hole Size 7 7/8 Slurry Wt. 14.7 Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting SPOT 25 SKS @ 3210' (Perfs 3220-3223')
 SPOT 15 SKS @ 1520'
 SPOT 25 SKS INSIDE OF 4 1/2 @ 260'
 SPOT 70 SKS outside on 4 1/2 w/ 1" Hy Drill
 135 SKS TOTAL (@ 262')

THANK YOU
 Russell McLoy

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	70	Mileage	3.95	276.50
C-203	135	60/40 Premix	12.75	1721.25
C-206	400 #	Gel = 2%	.20	80.00
C-108B	5.8	Tow's Tow Mileage 70 miles	1.35	548.10
C-110	262'	1" Hy Drill Rental	m/c	150.00
				3,525.85
			5%	187.52
			7.5%	264.44
Authorization <u>Witnessed by Scott Miller Title CO/Rep</u>			Total	3,600.77

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.