

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-031-19290-00-00
Spot: NWNESE Sec/Twnshp/Rge: 14-23S-14E
2396 feet from S Section Line, 332 feet from E Section Line
Lease Name: COCHRAN Well #: 2
County: COFFEY Total Vertical Depth: 1625 feet

Operator License No.: 6227
Op Name: KRAFT OIL COMPANY LLC
Address: 434 IRIS RD SW
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1625		50 SX
SURF	7.5	40		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2018 12:00 AM
Plug Co. License No.: 6227 Plug Co. Name: KRAFT OIL COMPANY LLC
Proposal Rcvd. from: THOMAS A. KRAFT Company: _____ Phone: (620) 836-2091

Proposed
Plugging
Method:

As per KCC instructions

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 04/17/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1570', pumped 20 sxs cement, pulled tubing to 552', pumped 15 sx cement, pulled tubing to 156', pumped 70 sxs cement to surface, casing sht @ 552' & 156', gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
APR 23 2018
CHANUTE, KS

MH

INVOICED

MAY 08 2018

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3858**
 Foreman Russell McCoy
 Camp Eureka

Apr 15-03/17 19290-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
4-17-18	1090	Cochran # 2	14	23	14	Coffey	Ks
Customer Kraft Oil Company L.L.C.			Safety Meeting		Unit #	Driver	Unit #
Mailing Address 434 Iris Road SW			RM		102	Rick	
City Gridley			Rich		113	AB	
State KS			AB		149	JASON	
Zip Code 66852			JAS		126	Russell	

Job Type P.T.A. Hole Depth _____ Slurry Vol. 26 Bbl Tubing 2 3/8
 Casing Depth 1670 Hole Size UNKNOWN Slurry Wt. 13.8 Drill Pipe _____
 Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting 20 SKs @ 1570'
15 SKs @ 552'
70 SKs @ 156' to Surface
105 SKs TOTAL

Good cement Returns to Surface.

Thank You
Russell McCoy

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105		Pump Charge	750.00	750.00
C-107	40	Mileage	3.95	158.00
C-203	105	SKs 60/40 P.2 mix	12.75	1338.75
C-206	360 ^{ft}	Gel = 49.	.20	72.00
C-108 B	4.5 Ton	X 40	1.35	243.00
C-113	2 hr	80 Bbl VAC Truck	85.00	170.00
				2,731.75
			-58	<145.46>
		Sales Tax		177.56

Authorization Witnessed by Tom Title owner Total 2163.85

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.