

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-031-19289-00-00
Spot: NENWNESE Sec/Twnshp/Rge: 14-23S-14E
2373 feet from S Section Line, 831 feet from E Section Line
Lease Name: COCHRAN Well #: 1
County: COFFEY Total Vertical Depth: 1630 feet

Operator License No.: 6227
Op Name: KRAFT OIL COMPANY LLC
Address: 434 IRIS RD SW
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1630		50 SX
SURF	8.6254	40		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2018 12:00 AM
Plug Co. License No.: 6227 Plug Co. Name: KRAFT OIL COMPANY LLC
Proposal Revd. from: THOMAS A. KRAFT Company: _____ Phone: (620) 836-2091

Proposed Plugging Method: AS per KCC instructions

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 04/17/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1574, pumped 20 sxs cement, pulled tubing to 579'. Pumped 15 sxs cement, pulled tubing to 158', pumped 50 sxs cement to surface, shot casing @ 579' & 158', gel spacers between cement plugs,

RECEIVED
KCC DIST # 3
APR 23 2018
CHANUTE, KS

MT

INVOICED

MAY 08 2018

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3859**
 Foreman Russell McCoy
 Camp Eureka

APT - 15-031-19289-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
4-17-18	1090	Cochran # 1	14	23	14	Coffey	Ks	
Customer Kenff Oil Company			Unit #		Driver		Unit #	Driver
Mailing Address 434 Iris Road			102		Rick			
City Gridley			113		AB			
State KS			145		JASON			
Zip Code 66852			126		Russell			

Job Type P.T.A. Hole Depth _____ Slurry Vol. 22 Tubing 2 3/8
 Casing Depth 1615 Hole Size _____ Slurry Wt. 13.0 Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting 20 SKs @ 1574'
15 SKs @ 579'
50 SKs @ 158' to surface.
85 SKs TOTAL

Good cement returning to surface.

Thank you
Russell McCoy

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-106	1.5	Pump Charge	200.00	300.00
		Mileage <u>no location</u>	N.C.	
C-203	85	SKs 60/40 Puzmix	12.75	1083.75
C-206	300 ^{ll}	Gel = 4%	.20	60.00
C-108B	3.65	Tow X 40	1.35	197.37
C-113	1 1/2	hr 80 Bbl Vac Truck	85.00	127.50
				1,768.62
			590	<94.8>
		Sales Tax		114.96
Authorization <u>witnessed by Tom</u> Title <u>owner</u>				Total <u>1789.40</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.