

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10026-00-00
Spot: SENW Sec/Twnshp/Rge: 21-22S-41W
3327 feet from S Section Line, 3130 feet from E Section Line
Lease Name: HCU (SPARR 1) Well #: 2121
County: HAMILTON Total Vertical Depth: 2697 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 1205 | | |
| PROD | 4.5 | 2696 | 0 | WITH 100 SX CMT |
| SURF | 8.625 | 197 | | WITH 150 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/17/2018 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2018 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK. RAN FREE POINT. STUCK AT 2300'. FREE AT 2200'. CUT TBG AT 2200'. SPOT 35 SX CMT WITH 150# HULLS AT 2170'. TOO H WITH TBG. SET CIBP @ 1205' TO COVER CASING LEAK. LOAD & TEST CASING TO 800#. HOLDING. RAN CBL FROM 1200'. FOUND TOP OF GOOD CMT AT 880' WITH CMT STRINGERS TO 800'. PERFORATE 4 HOLES AT 350'. INJECTION RATE 2 BPM AT 250#. RUN TBG TO 1152' & CIRCULATE CMT TO SURFACE UP THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS WITH 180 SX CMT. TOO H WITH TBG & TOP OFF WITH 35 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2622 | 2666 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: TBG

INVOICED

MAY 08 2018

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
APR 24 2018
KCC DODGE CITY

SA

Form CP-2/3