

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-00130-00-00  
Spot: SWNE Sec/Twnshp/Rge: 29-22S-40W  
3295 feet from S Section Line, 2034 feet from E Section Line  
Lease Name: HCU (JIRS GRACE 1) Well #: 2920  
County: HAMILTON Total Vertical Depth: 2702 feet

Operator License No.: 33999 String Size Depth (ft) Pulled (ft) Comments  
Op Name: LINN OPERATING, LLC PROD 4.5 2705 0 WITH 150 SX CMT  
Address: 600 TRAVIS STE 1400 SURF 8.625 216 WITH 250 SX CMT  
HOUSTON, TX 77002

Well Type: OG UIC Docket No: Date/Time to Plug: 04/13/2018 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (713) 904-6537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2018 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAKS AT 1280' TO 1435' SQUEEZED IN 1993 WITH UNKNOWN SACKS. PUMP 75 SX CMT WITH 250# HULLS DOWN 4 1/2" CASING. DISPLACE CMT TO 1450' WITH BOTTOM OF CMT AT 2650'. PRESSURE TO 300#. HOLDING. RUN CBL FROM 1400' TO 0'. FOUND TOC @ 216'. PERFORATE 4 HOLES AT 210'. RUN TBG TO 1162'. CIRCULATE CMT TO SURFACE WTH 140 SX CMT. TOOH WITH TBG & TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2643	2650		
2634	2638		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: TBG

INVOICED  
MAY 08 2018

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
APR 24 2018  
KCC DODGE CITY