

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20411-00-00
Spot: NW Sec/Twnshp/Rge: 16-23S-41W
3986 feet from S Section Line, 3965 feet from E Section Line
Lease Name: HCU Well #: 1631-B
County: HAMILTON Total Vertical Depth: 5400 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2000		
DVT		2647		WITH 325 SX CMT
PROD	5.5	4422	0	WITH 600 SX CMT
SURF	8.625	903		WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/18/2018 12:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2018 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 85 SX CMT WITH 250# HULLS DOWN 5 1/2" CASING. DISPLACE TO 2475'. TAG WITH WIRELINE. SET CIBP @ 2000'. RUN CBL. FOUND TOC @ 1770'. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 1005'. INJECTION RATE 2 BPM @ 250#. CIRCULATE CMT TO SURFACE USING 230 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2486	2499		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 24 2018
KCC DODGE CITY