

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20748-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 25-21S-42W
1250 feet from N Section Line, 1250 feet from E Section Line
Lease Name: HCU Well #: 2512-C
County: HAMILTON Total Vertical Depth: 2930 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2925	0	WITH 550 SX CMT
SURF	8.625	315		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/11/2018 9:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2018 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PLUGGED DOWN 4 1/2" CASING AS FOLLOWS: 40 SX CMT WITH 200# HULLS FROM 2777' TO 2100'. 10 BBL SPACER FROM 2100' TO 1470'. 105 SX CMT FROM 1470' TO 0'. PRESSURE TO 400#. HOLDING. 5 SX CMT DOWN ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
2762	2777		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

INVOICE
MAY 08 2018

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
APR 16 2018
KCC DODGE CITY