

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20452-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 2-24S-41W
1269 feet from S Section Line, 1731 feet from E Section Line
Lease Name: HCU Well #: 0241-B
County: HAMILTON Total Vertical Depth: 2458 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2457	0	WITH 325 SX CMT
SURF	8.625	359		WITH 230 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/11/2018 11:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PUMP 50 SX CMT WITH 200# HULLS FROM 2320'-1500'. 8 BBL SPACER FROM 1500'-1000'. 70 SX CMT FROM 1000' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2018 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PLUGGED DOWN 4 1/2" CASING AS FOLLOWS: 50 SX CMT WITH 200# HULLS FROM 2320' TO 1500'. 8 BBL SPACER FROM 1500' TO 1000'. 80 SX CMT FROM 1000' TO 0'. PRESSURE TO 400#. HOLDING. 20 SX CMT DOWN THE ANNULUS TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2311	2320		


Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

INVOICED
MAY 08 2018

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 16 2018
KCC DODGE CITY