

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20404-00-00
Spot: SW Sec/Twnshp/Rge: 17-23S-40W
1338 feet from S Section Line, 3969 feet from E Section Line
Lease Name: HCU Well #: 1730-B
County: HAMILTON Total Vertical Depth: 2843 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2842	0	WITH 610 SX CMT
SURF	8.625	233		WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/11/2018 12:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: STAN COUCHMAN Company: CONSOLIDATED OIL WELL SERVI Phone: (620) 356-6961

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS FROM 2548' TO 1750'. 9 BBL SPACER FROM 1750' TO 1200'. PUMP 80 SX CMT FROM 1200' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2018 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PLUGGED DOWN 4 1/2" CASING AS FOLLOWS: 50 SX CMT WITH 200# HULLS FROM 2548' TO 1750'. 9 BBL SPACER FROM 1750' TO 1200'. 80 SX CMT FROM 1200' TO 0'. PRESSURE TO 400#. HOLDING. 25 SX CMT DOWN THE ANNULUS. PRESSURE TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2718	2726		
2625	2630		
2576	2582		
2528	2548		


Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

INVOICED
MAY 08 2018

District: 01

Signed



(TECHNICIAN)

SA

RECEIVED
APR 16 2018
KCC DODGE CITY

Form CP-2/3