

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20479-00-01  
Spot: SE Sec/Twnshp/Rge: 31-22S-40W  
1319 feet from S Section Line, 1286 feet from E Section Line  
Lease Name: HCU Well #: 3120-C  
County: HAMILTON Total Vertical Depth: 2727 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, LLC  
Address: 600 TRAVIS STE 1400  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2727	0	WITH 625 SX CMT
SURF	8.625	360		WITH 220 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2018 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/10/2018 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PLUGGED WELL DOWN 4 1/2" CASING AS FOLLOWS: 50 SX CMT WITH 200# HULLS FROM 2690' TO 1900'. 10 BBL SPACER FROM 1900' TO 1300'. 100 SX CMT FROM 1300' TO 0'. PRESSURE TO 400#. HOLDING. 5 SX CMT DOWN THE ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
2570	2590		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
APR 16 2018  
KCC DODGE CITY

INVOICED

MAY 08 2018