

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20226-00-00  
Spot: NESW Sec/Twnshp/Rge: 5-22S-41W  
1992 feet from S Section Line, 3299 feet from E Section Line  
Lease Name: HCU Well #: 0521-B  
County: HAMILTON Total Vertical Depth: 2850 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, LLC  
Address: 600 TRAVIS STE 1400  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2849	0	WITH 550 SX CMT
SURF	8.625	252		WITH 175 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2018 10:30 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: STAN COUCHMAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: 50 SX CMT FROM 2763'-2000'. 10 BBL SPACER FROM 2000'-1400'. 100 SX CMT FROM 1400'-0'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/10/2018 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PLUGGED DOWN 4 1/2" CASING AS FOLLOWS: 50 SX CMT WITH 200# HULLS FROM 2763' TO 2000'. 10 BBL SPACER FROM 2000' TO 1400'. 95 SX CMT FROM 1400' TO 0'. PRESSURE TO 400#. HOLDING. 10 SX CMT DOWN THE ANNULUS TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2757	2763		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.


Plugged through: CSG

INVOICED

MAY 08 2018

District: 01

Signed



(TECHNICIAN)

RECEIVED  
APR 16 2018  
KCC DODGE CITY