

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20444-00-00
Spot: SE Sec/Twnshp/Rge: 14-21S-41W
1352 feet from S Section Line, 1349 feet from E Section Line
Lease Name: HCU Well #: 1411-C
County: HAMILTON Total Vertical Depth: 2900 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2903	0	WITH 825 SX CMT
SURF	8.625	367		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/12/2018 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUG AT 2700' WITH 50 SX CMT & 200# HULLS. PULL UP TO 1500' & LOAD & TEST CASING. IF IT DOESN'T HOLD: PLUG AT 1500' WITH 25 SX CMT & 150# HULLS. PLUG AT 1222' WITH 110 SX CMT TO 0'. PUMP 5 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2018 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

1ST PLUG AT 2707' WITH 50 SX CMT & 200# HULLS. WELL WOULD NOT HOLD PRESSURE. 2ND PLUG AT 1509' WITH 25 SX CMT & 200# HULLS. 3RD PLUG AT 1222' WITH 110 SX CMT TO 0'. 4TH PLUG PUMP 5 SX CMT DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
2776	2790		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: TBG

District: 01

Signed

Kenny Sullivan

(TECHNICIAN)

SA

RECEIVED
APR 16 2018
KCC DODGE CITY

INVOICED
MAY 08 2018