

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-26643-00-00  
Spot: SESWNESW Sec/Twnshp/Rge: 22-11S-19W  
1575 feet from S Section Line, 1785 feet from W Section Line  
Lease Name: M.R. ALLEN Well #: 14  
County: ELLIS Total Vertical Depth: 3640 feet

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: PO BOX 1121  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3634		350 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2018 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: RODNEY BRIN Company: MUSTANG ENERGY CORPORATIO Phone: (785) 623-0533

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 8 sx gel and 500 # hulls.  
Alt II top to bottom. PBSD 3610'.  
Heartland took pump in rate 3 bbl per min.  
Perforations: LKC ARB OH - 3571' - 3573', 3580' - 3582'.  
Perforations: LKC H: 3404', I: 3424', J: 3436', K: 3463', C: 3307', D: 3326', E: 3345' - 3348'.  
Ordea: 3194' - 3196', Marmaton: 3513' - 3517'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2018 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to 5 1/2" casing and pumped 100 sx cement w/400 # hulls followed by 8 sx gel, followed by 120 sx cement w/100 # hulls mixed in. Pumped to pressure with 600 psi. Shut in pressure 500 psi. Rigged to 8 5/8" surface casing and pumped 5 sx cement w/200 psi. Shut in pressure 200 psi.

Perfs:


Top	Bot	Thru	Comments
3571	3582		
3513	3517		
3307	3463		
3194	3196		

Remarks: QUALITY OILWELL CEMENTING TICKET # 745

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

CM

APR 20 2018

Form CP-2/3

4-30-18  
KCC WICHITA  
APR 30 2018  
RECEIVED  
MAY 08 2018