

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21143-00-00
Spot: SWSSESWNW Sec/Twnshp/Rge: 11-33S-19W
2530 feet from N Section Line, 980 feet from W Section Line
Lease Name: DEEWALL Well #: 1
County: COMANCHE Total Vertical Depth: 6372 feet

Operator License No.: 33185
Op Name: QUAIL OIL & GAS, LC
Address: 525 INDUSTRIAL DR. PO BOX K
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5042		WITH 2 SX CMT
CIBP		5250		
CIBP		5740		
PROD	5.5	6360	2452	WITH 90 SX CMT
SURF	8.625	692		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/24/2018 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DARON PATTERSON Company: QUAIL OIL & GAS Phone: (620) 539-0464

Proposed Plugging Method: Set CIBP at 5042' w/ 2 sacks cement. Shoot casing and pump cement plugs casing. 50 sacks at 1120' 50 sacks at 720' 30 sacks at 260' 20 sacks at 40'

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 04/24/2018 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5042' WITH 2 SX CMT. 1ST PLUG AT 1110' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 718' WITH 50 SX CMT. 3RD PLUG AT 261' WITH 30 SX CMT. 4TH PLUG AT 65' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6004	6008		
5278	5362		
5174	5180		
5092	5098		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

INVOICE
MAY 08 2018

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
APR 25 2018
KCC DODGE CITY