

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-151-10730-00-00
 Spot: SWNESE Sec/Twnshp/Rge: 6-26S-13W
1586 feet from S Section Line, 1005 feet from E Section Line
 Lease Name: SMITH FRED Well #: 2
 County: PRATT Total Vertical Depth: 4432 feet

Operator License No.: 5120
 Op Name: RANGE OIL COMPANY, INC.
 Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		WITH 5 SX CMT
CIBP		3998		
PROD 7		4400	0	WITH 200 SX CMT
SURF	10.75	508		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2018 10:00 AM
 Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
 Proposal Rcvd. from: ALAN NATION Company: GRESSEL OILFIELD SERVICE, LLC Phone: (620) 222-4304

Proposed Plugging Method: CIBP @ 3800' WITH 5 SX CMT. PERFORATE AT 950' WITH 80 SX CMT & 100# HULLS IN LAST 40 SX CMT. PERFORATE AT 550' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 04/18/2018 4:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3800' WITH 5 SX CMT ON TOP. PERFORATE AT 950' & 550'. PICK UP TBG & TIH TO 950'. PUMP 80 SX CMT WITH 100# HULLS IN LAST 40 SX. PULL TBG TO 550'. PUMP 207 SX CMT TO FILL CASING TO SURFACE & 106 SX CMT TO FILL ANNULUS. PULL TBG & TOP OFF HOLE WITH 15 SX CMT. CMT FELL BACK TO ABOUT 10'.

Perfs:

Top	Bot	Thru	Comments
3986	3992		
3970	3976		
3905	3909		
3848	3858		

INVOICED
 MAY 08 2018

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed Ken Scofield
 (TECHNICIAN)

RECEIVED
 APR 26 2018
 KCC DODGE CITY