

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: **15-151-10732-00-00**  
Spot: SWNWSE Sec/Twnshp/Rge: 6-26S-13W  
1615 feet from S Section Line, 2328 feet from E Section Line  
Lease Name: SMITH FRED Well #: 4  
County: PRATT Total Vertical Depth: 4085 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   | 7     | 3800       |             | WITH 5 SX CMT   |
| PROD   | 7     | 4084       | 0           | WITH 225 SX CMT |
| SURF   | 10.75 | 602        |             | WITH 450 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2018 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 3800' & 5 SX CMT ON TOP. PERFORATE 7" AT 950' & 620'. RUN TBG INTO 950' & PUMP 40 SX CMT, 100# HULLS & 40 SX CMT. PULLED TBG UP TO 620' & CIRCULATE CMT TO SURFACE ON THE 7" X 10 3/4" ANNULUS & INSIDE THE 7" CASING.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/16/2018 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3800' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 7" CASING AT 950' & 620'. RUN TBG IN TO 932'. PUMP DOWN TBG WITH 80 SX CMT & 100# HULLS PUTTING 40 SX CMT OUTSIDE 7" CASING & LEAVING 40 SX CMT INSIDE 7" CASING. PULL TBG UP TO 620'. PUMP DOWN TBG WITH 245 SX CMT. CMT CIRCULATED TO SURFACE FILLING INSIDE & OUTSIDE OF 7" CASING. LAID DOWN TBG & TOP OFF WITH 40 SX CMT. 4/19/18: TOP OFF 7" CASING WITH 45 SX CMT AND 7" X 10 3/4" ANNULUS WITH 40 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4026 | 4032 |      |          |
| 3950 | 3958 |      |          |
| 3902 | 3907 |      |          |
| 3845 | 3850 |      |          |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

INVOICED

MAY 08 2018

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
APR 26 2018  
KCC DODGE CITY