

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21162-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 32-12S-16W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WINDHOLZ Well #: 1
County: ELLIS Total Vertical Depth: 3537 feet

Operator License No.: 5252
Op Name: R. P. NIXON OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3532		125 SX
SURF	8.625	184		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2018 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DUANE ATCHERBERG Company: R. P. NIXON OPERATIONS, INC Phone: (785) 656-0038

Proposed Plugging Method: Ordered 310 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforated at 1140' w/265 sx cement to surface.
Casing leaks from 2100' - 2500'.
Perforations: Shaw 3276' - 3297' OA and LKC 3338' - 3429'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2018 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Express Well Service ran in hole with tubing to 3285'. Quality rigged to tubing and pumped 108 sx cement w/300 # hulls mixed in. Pulled tubing to 1650'. Quality rigged to tubing and pumped 135 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Rigged to 4 1/2' casing with a swage and pumped 15 sx cement w/300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" casing and pumped 50 sx cement w/200 psi. Shut in pressure 100 psi.

GPS: 38.96114 -099.12161

Remarks: QUALITY WELL CEMENTING CO TICKET # 742

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

APR 10 2018

Form CP-2/3

4-30-18
KCC WICHITA
APR 30 2018
RECEIVED

INVOICE

MAY 08 2018