

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-26448-00-00  
Spot: SEWNENE Sec/Twnshp/Rge: 10-29S-16E  
1983 feet from S Section Line, 667 feet from E Section Line  
Lease Name: PHILLIP D. CARTER Well #: 1-10  
County: WILSON Total Vertical Depth: 1155 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1147		135 SX
SURF	8.625	22		4 SX
TI	2.375	1147		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2018 9:30 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 205-8510

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 04/10/2018 9:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from btm to top. The cement string was removed and the well topped off. According to operator, a total of 115 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
894	896		
854	856		
750	753		
667	671		
654	658		

RECEIVED  
KCC DIST # 3  
MAY 02 2018  
CHANUTE, KS

AD

INVOICED

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)