

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-26467-00-00  
Spot: NESWSESE Sec/Twnshp/Rge: 23-28S-17E  
650 feet from S Section Line, 698 feet from E Section Line  
Lease Name: HARDIN, CAROLINE M. Well #: 23-3  
County: NEOSHO Total Vertical Depth: 1238 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1234		151 SX
SURF	8.625	24		5 SX
T1	2.375	1155		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2018 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 04/09/2018 12:00 PM KCC Agent: ALAN DUNNING

**Actual Plugging Report:**

A cement string was lowered to 1140 ft and the well pumped full of cement from btm to top. The cement string was pulled to 200 ft and the well again pumped full of cement. The cement string was removed and the well topped off. A total of 115.5 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

**Perfs:**

Top	Bot	Thru	Comments
1137	1140		
1086	1088		
992	993		
848	851		
829	831		
766	771		
753	757		

RECEIVED  
KCC DIST # 3  
MAY 02 2018  
CHANUTE, KS

AD

INVOICED

MAY 08 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)