

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-27227-00-00  
Spot: N2S2SWNW Sec/Twnshp/Rge: 24-28S-18E  
1981 feet from N Section Line, 660 feet from W Section Line  
Lease Name: CHEYNEY LAND Well #: 24-3  
County: NEOSHO Total Vertical Depth: 1118 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1101		155 SX
SURF	8.625	20		5 SX
T1	2.375	1016		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2018 10:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 205-8510

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 04/09/2018 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1070' and the well pumped full of cement from btm to top. The cement string was pulled to 200' and the well again pumped full of cement. The cement string was pulled and the well topped off. According to operator, 105 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
996	999		
939	941		
934	936		
833	835		
782	784		
756	758		
744	746		
729	731		
688	691		
582	586		
570	574		

RECEIVED  
KCC DIST # 3  
MAY 02 2018  
CHANUTE, KS

AD  
INVOICE

MAY 08 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning  
(TECHNICIAN)