

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-21458-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 10-16S-17W  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: URBAN Well #: 1  
County: RUSH Total Vertical Depth: 3620 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3250		WITH 2 SX CMT
CIBP		3535		
DVT	4.5	2128		WITH 100 SX CMT
PROD	4.5	3619	0	WITH 275 SX CMT
SURF	8.625	965		WITH 375 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2018 10:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: CIBP 50' ABOVE PERFS THEN PERFORATE AT 1000' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/28/2018 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3250' WITH 2 SX CMT. PERFORATED AT 1000'. TIED ONTO CASING & PUMPED 180 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3575	3580		
3289	3494		

INVOICED  
MAY 02 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY QUALIY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAR - 6 2018  
KCC DODGE CITY

KMS  
Form CP-2/3