

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21219-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 6-16S-33W
1978 feet from S Section Line, 1942 feet from W Section Line
Lease Name: DOG POUND Well #: #1-0118
County: SCOTT Total Vertical Depth: 4840 feet

Operator License No.: 35530
Op Name: TEXAS TEA OIL & GAS LLC
Address: 5920 HEMLOCK DR.
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	303		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/01/2018 6:30 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: SID DEUTSCHER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 810' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD WitnessType: NONE
Date/Time Plugging Completed: 03/01/2018 8:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 810' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

INVOICED


MAY 02 2018

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY GLOBAL.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR - 9 2018
KCC DODGE CITY

