

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24644-00-00
Spot: NWNWSENW Sec/Twnshp/Rge: 26-19S-14W
1485 feet from N Section Line, 1485 feet from W Section Line
Lease Name: OPIE Well #: 4
County: BARTON Total Vertical Depth: 3565 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3562		175 SX
SURF	8.625	800		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2018 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOHN THOMAS Company: THOMAS, JOHN R. DBA VAMCO O Phone: (620) 793-2604

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Cement order was for 5 1/2" casing. Head was dug out and 4 1/2" casing was found.
Vamco used a rig owned by them.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2018 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 770'. Ran tubing to 3410' and pumped 5 sx gel followed by 40 sx cement. Pulled tubing to 2000' and pumped 70 sx cement. Pulled tubing to 1000' and pumped 50 sx cement. Pulled tubing to 300'. Circulated cement to surface on casing with 130 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 50 sx cement.

GPS: 38.37209 -098.84310

Perfs:

Remarks: QUALITY WELL SERVICE

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CJM

Received
KANSAS CORPORATION COMMISSION

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

INVOICED
MAY 02 2018

APR 09 2018

Form CP-2/3