

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22322-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 2-14S-29W
740 feet from S Section Line, 1292 feet from E Section Line
Lease Name: POWERS Well #: 16B-2-1429
County: GOVE Total Vertical Depth: 4570 feet

Operator License No.: 35233
Op Name: US OIL RESOURCES LLC
Address: 6727 W. PRENTICE AVE
LAKWOOD, CO 80123

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		175 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/04/2018 12:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: ADAM BLUM Company: DUKE DRILLING CO., INC. Phone: (720) 989-9090

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 02/04/2018 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2175 w/50 sx
2nd plug @1175 w/100 sx
3rd plug @300 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: CONSOLIDATED

Plugged through: DP

KCC WICHITA
MAR 16 2018
INVOICED RECEIVED
MAY 02 2018

District: 04

Signed _____



(TECHNICIAN)

MAR 01 2018