

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21182-00-00
Spot: SWNENW Sec/Twnshp/Rge: 19-32S-28W
4284 feet from S Section Line, 3600 feet from E Section Line
Lease Name: CLAWSON Well #: 2-19
County: MEADE Total Vertical Depth: 5680 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5664	1705	WITH 165 SX CMT
SURF	8.625	1645		WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/13/2018 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING Phone: (316) 262-2502

Proposed Plugging Method: CIBP @ 5450' WITH 3 SX CMT. PRESSURE TEST CASING TO 200#. PLUG AT 1700' WITH 12 SX GEL & 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2018 2:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

SET CIBP @ 5450' WITH 3 SX CMT. PRESSURE TEST CASING TO 200#. 1ST PLUG AT 1700' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE. TOPPED OFF WITH 10 SX CMT.

Top	Bot	Thru	Comments
5508	5515		
5499	5503		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Larry Harris ECRS
(TECHNICIAN)

SA

RECEIVED
MAR 20 2018
KCC DODGE CITY

MD