

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22178-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 32-14S-18W
4250 feet from S Section Line, 3732 feet from E Section Line
Lease Name: ROHR Well #: 3
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 5798
Op Name: WEILERT, MICHAEL D. DBA MICHAEL
Address: 866 230TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3672		
SURF	8.625	350		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2018 11:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: MICHAEL D. WEILERT Company: WEILERT OIL COMPANY Phone: (785) 625-6327

Proposed Plugging Method: Ordered 335 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Operator pulled rods. Tubing stuck in hole. Emergency plug with rig over hole.
DV Tool at 1250' with unknown amount of cement. Operator said well had a temperature survey showing cement from 1250' to 250' approved by Don Butcher.
PBTB 3606'. Plug over Arbuckle.
Perforations: 3368' - 3372', 3495' - 3501' and 3672' - 3673'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2018 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Pioneer Logging Service did free point indicating free tubing at 2700'. Operator pulled tubing apart at 488'. 15 1/2 joints of tubing recovered. Operator will attempt to recover more tubing on 03/05/2018.
03/07/2018 - Recovered a total of 2275' of tubing.
03/08/2018 - Ran in hole with tubing to 2245' and pumped 125 sx cement. Pulled tubing to 1800' and pumped 80 sx cement w/300 # hulls to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swage and pumped 20 sx cement w/500 psi. Shut in pressure 500 psi.
Rigged to 8 5/8" casing and pumped 20 sx cement w/200 psi. Shut in pressure 200 psi.
GPS: 38.79570 -099.35031

Perfs:

Top	Bot	Thru	Comments
3672	3673		
3495	3501		
3368	3372		

Remarks: GLOBAL CEMENTING CO TICKET # 3144


Plugged through: TBG

INVOICED

MAY 03 2018

District: 04

Signed _____



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAR 13 2018