

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22144-00-00
Spot: W2SESE Sec/Twnshp/Rge: 33-15S-29W
660 feet from S Section Line, 990 feet from E Section Line
Lease Name: DOWELL I Well #: 2
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4100		200 SX
SURF	8.625	352		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2018 1:30 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM, INC. DBA Phone: (620) 628-4466

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.
Perforations: 3850' - 3853', 3898' - 3901'.
Port Collar set at 1978' w/175 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2018 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3850' and pumped 14 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 2007' and pumped 230 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 350 psi.

GPS: 38.70188 -100.54526

Perfs:

Top	Bot	Thru	Comments
3898	3901		
3850	3853		

Remarks: SWIFT CEMENT TICKET # 31347

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

APR 07 2018

APR 16 2018

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS