

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-22277-00-00  
Spot: SWSWNWNW Sec/Twnshp/Rge: 35-7S-23W  
4071 feet from S Section Line, 5207 feet from E Section Line  
Lease Name: KORB Well #: 1  
County: GRAHAM Total Vertical Depth: 3820 feet

Operator License No.: 4656 String Size Depth (ft) Pulled (ft) Comments  
Op Name: DAVIS PETROLEUM, INC. PROD 4.5 3818 300 SX  
Address: 7 SW 26 AVE SURF 8.625 314 200 SX  
GREAT BEND, KS 67530

Well Type: EOR UIC Docket No: E24567.1 Date/Time to Plug: 03/06/2018 10:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: SCHIPPERS CEMENT S.O.S. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Alt II: 1952' w/300 sx cement.  
Perforations: 3730' - 3731', 3738' - 3740' and 3760' - 3761'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/07/2018 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 300 sx cement w/300 # hulls. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 150 psi. Topped off casing with 30 sx cement. Cement was falling. Shut down for the day.  
03/07/2018 - Topped off casing with 30 sx cement.

GPS: 39.40475 -099.86364

Perfs:

Top	Bot	Thru	Comments
3760	3761		
3738	3740		
3730	3731		

Remarks: SCHIPPERS CEMENT S.O.S. TICKET # 622


Plugged through: CSG

KCC WICHITA  
MAR 16 2018  
RECEIVED  
INVOICED

MAY 0 1 2008

District: 04

Signed



(TECHNICIAN)

CM

MAR 12 2008