

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-00159-00-01
Spot: SWSWNESE Sec/Twnshp/Rge: 18-29S-18W
1347 feet from S Section Line, 1306 feet from E Section Line
Lease Name: GREY Well #: 1-SWD
County: KIOWA Total Vertical Depth: 5122 feet

Operator License No.: 3344
Op Name: MAGNUM OIL & GAS
Address: 8520 25TH AVE
GREENSBURG, KS 67054

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		2732		
PROD	4.5	5120	1270	WITH 200 SX CMT
SURF	8.625	360		WITH 100 SX CMT

Well Type: SWD UIC Docket No: D23768.0 Date/Time to Plug: 03/23/2018 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 723-2463

Proposed Plugging Method: SAND TO 2700' WITH 4 SX CMT. PLUG AT 1320' WITH 12 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2018 11:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PBTD: 3000'. R-4 PACKER SET AT 2732'. ESTINATED TOP OF CMT AT 2400'.
SANDED TO 2680' & DUMPED 4 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT
1270' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD
PLUG AT 40' WITH 35 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
2750	2870		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

INVOICED
MAY 02 2018

District: 01

Signed  (TECHNICIAN)

RECEIVED
MAR 26 2018
KCC DODGE CITY

