

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19671-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 19-23S-9E
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCOTT Well #: S 5
County: GREENWOOD Total Vertical Depth: 2687 feet

Operator License No.: 34503
Op Name: SAM W. MAYS JR. LLC DBA MAYS OIL
Address: PO BOX 391
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2687		100 SX
SURF	5.625	208		100 SX

Well Type: EOR UIC Docket No: E01264.3 Date/Time to Plug: 03/13/2018 9:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Revd. from: SAM MAYS Company: Phone: (918) 382-9170

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2018 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Iron in well bore @ 1440', unable to retrieve or move past, gel in hole from 1440 to surface, shot casing @ 900' & 150', ran tubing to 1400' pumped 40 sxs cement, pulled tubing to 150', pumped 160 sxs cement to surface,

Perfs:

Top	Bot	Thru	Comments
2593	2634		

RECEIVED
KCC DIST # 3
MAR 19 2018
CHANUTE, KS

MT

INVOICED


Remarks:

MAY 02 2018

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

810 E 7th
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-073-19671 0000
Cement or Acid Field Report
 Ticket No. **3782**
 Foreman Russell McInoy
 Camp Eureka

APF[#] 15-073-19671-00-00

Date	Cust. ID#	Lease & Well Number	Section	Township	Range	County	State	
3-13-18	1080	Scott 5-5	19	23	9	G.w.	Ks	
Customer Sam Mays JR			Safety Meeting Rm RICK JASON STEVE ALAN		Unit #	Driver	Unit #	Driver
Mailing Address Po. Box 391					102	RICK		
City Eureka					110	JASON		
State KS					145	STEVE		
Zip Code 67045					144	ALAN M		

Job Type PT.A. (OIL WELL) Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8 / "
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Well Information
 Perf (A) 900'
 Perf (A) 150'
 Tubing Into (A) 1400'
 SPOT 4 SKI Gel @ 1400'
 SPOT 40 SKI @ 1370 up to 850'
 SPOT 110 SKI 150 to SURFACE
 1" Down Annulus of 5 1/2 to 150'
 1" Down INSIDE of 5 1/2 to 150'
 CASING Full Annulus Full Job Complete

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	30	Mileage	3.95	118.50
C-203	200 SKI	60/40 Pozmix	12.75	2,550.00
C-206	680 #	Gel = 4%	.20	136.00
C-206	200 #	Gel	.20	40.00
C-214	45 #	cottonseed Hulls) SPOT (A) 1400'	.45	20.25
C-113	5 hr	80 BBI VAC TRUCK 145	85.00	425.00
C-113	2 hr	80 B6 VAC TRUCK 144 (empty Pit)	85.00	170.00
			Sub TOTAL	4209.75
			Sales Tax	315.73

Authorization by SAM MAYS Title OWNER Total 4525.48

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.