

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20408-00-01
Spot: SWSWNENE Sec/Twnshp/Rge: 23-29S-19W
4005 feet from S Section Line, 1241 feet from E Section Line
Lease Name: NEWBY Well #: 1
County: KIOWA Total Vertical Depth: 5130 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		WITH 3 SX CMT
CIBP		4185		
PROD	5.5	5124	0	WITH 100 SX CMT
SURF	8.625	541		WITH 350 SX CMT

Well Type: SWD UIC Docket No: D24385.0 Date/Time to Plug: 03/09/2018 1:00 PM
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.
Proposal Rcvd. from: SPENCER SIROKY Company: FOSSIL DRILLING, INC. Phone: (620) 770-0636

Proposed Plugging Method: CIBP @ 3850' WITH 3 SX CMT. PRESSURE TEST CASING. CUT & PULL CASING. PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. PLUG AT 590' WITH 50 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2018 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

3/9/18: WITNESSED BY ERIC MACLAREN. SET CIBP @ 3850' WITH 3 SX CMT. PRESSURE TESTED CASING & HELD AT 300#. COULD NOT GET ANY STRETCH ON THE PRODUCTION CASING. PERFORATED AT 1250'. SPOTTED 50 SX CMT (1/2 INSIDE & 1/2 OUTSIDE) THROUGH PERFORATIONS. PERFORATED AT 590'. PUMPED 210 SX CMT. HAD GOOD RETURNS UNTIL A SHOW OF CMT THEN LOST CIRCULATION. SHUT DOWN FOR WEEKEND. 3/12/18: WITNESSED BY LARRY HARRIS. TAGGED TOC @ 1000' INSIDE OF 5 1/2". LOADED CASING & ATTEMPTED TO PUMP THROUGH PERFORATIONS BUT COULD NOT. RAN CEMENT BOND LOG AND FOUND CMT 60' FROM SURFACE. RAN TBG TO 600' & CIRCULATED CMT TO SURFACE WITH 65 SX CMT. PULLED TBG & TOPPED OFF WITH 6 SX CMT. RAN 60' OF 1" & PUMPED 14 SX CMT DOWN ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3999	4009		
3920	3930		
3898	3908		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed

Larry A Harris ECRS
(TECHNICIAN)

RECEIVED
MAR 20 2018
KCC DODGE CITY

SA

INVOICED

MAY 03 2018