

4- 062610

4-3

68-
R

15.009.20204.0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 3-4-68

SW SE NW /4 SEC. 31, 20 S, 12 W
2970 feet from S section line
3630 feet from E section line

Operator license# 07054

Lease Spacil well # A-1

Operator: Doonan & Sons, Inc.

County Barton

Address: P.O. Box 1286
Great Bend, Kansas 67530
316-792-2191

Well total depth 3515 feet ^{114.23}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 1:00P.M. Day: 3 Month: April Year: 92

Plugging proposal received from: Claude Blakesley

Company: Doonan & Sons, Inc. Phone: 316-938-2943

Were: Order 200 sks. of 60/40 pozmix - 8% gel. - 5 sks. hulls.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 1992

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:00P.M., Day: 3, Month: April, Year: 92

Actual plugging report: 8 5/8" @ 219' w/200 sks. 5 1/2" @ 3514'
w/100 sks. Top perf. @ 3471'. Plugged bottom with sand and 5 sks.
cement to 3400'. Shot pipe 10 times and recovered 1700'. Pump in
5 1/2" casing and circulated cement from 750' to surface. Hooked on
to 8 5/8" and squeezed to 500 P.S.I. Pulled all casing and used
200 sks. cement.

Max. pressure on 5 1/2" - 500 P.S.I. Shut in @ 400 P.S.I.
Max. pressure on backside - 300 P.S.I. Shut in @ 100 P.S.I.

Total sacks 200 cement.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES 725 NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1856 GL

I did [X] / did not [] observe the plugging.

Gilbert G. Scheck

DATE 4-28-92

(agent)

INV. NO. 35081

Form CP-2/3