

6 070327

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5 1/2 - NW - SE, SEC. 21, T 20 S, R 12 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111
Operator: FOUR MAN OPERATIONS
ROCKHOLD ENGINEERING
Name & Address: BOX 698
GREAT BEND, KANS.
67530

feet from S section line

feet from E section line

Lease Name PHILLIPS Well # 3

County BARTON 113.10

Well Total Depth 3480 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor ROCKHOLD ENGINEERING License Number 5111

Address BOX 698 - GREAT BEND, KANS. 67530

Company to plug at: Hour: 1:00 PM Day: 5th Month: MARCH Year: 19 85

Plugging proposal received from DECON PULLY AND DON BUTCHER (KOH)

(company name) ROCKHOLD ENGINEERING (phone) 316-792-2506

were: 8 5/8" 240 FT SP. CML M/NA., 4 1/2" CSG SET @ 3480 FT M/NA.

PERFS WERE @ 3424' TO 3428', MY ROCKHOLD SAID 4 1/2" WAS PLUGGED BACK @ 2470'

THERE WERE HOLES UP AND DOWN CSG, 4 1/2" WAS SQUEEZED AMOUNT OF CMT UNKNOWN

CEMENT REMAINED IN HOLE. UP TO 340 FT, ROCKHOLD RAN 1" TUBING TO 340 FT COULDN'T

GET DOWN ANY FURTHER, ORDER 50^{SK} 50/50 Pozmix 4% 3% GEL - CA-CL, LOAD 4 1/2" CSG WITH

CMT AND PRESURE ANNULUS Plugging Proposal Received by BOIC (TECHNICIAN)

WITH CEMENT.

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 PM Day: 5th Month: MARCH Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 50^{SK} 50/50 Pozmix 4% 3% GEL - CA-CL,

RAN 1" TUBING TO 340 FT SPOTTED AN CIRCULATED M/30^{SK} CMT.

1" TUBING STUCK IN HOLE, BACHED OFF 1 JOINT AND REMOVED IT.

TIED ON TO 4 1/2" CSG AND LOADED HOLE TO ^{TOP} AND SQUEEZED M/10^{SK} CMT.

450 Psi.g, - PUMPED IN ANNULUS 6^{SK} CMT. SHUT IN MAX 500 Psi.g.

CEMENTED BY ALLIED CEMENTING - GREAT BEND, MO.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____

If additional description is necessary, use BACK of this form. MAR 11 1985

INVOLVED

(did, ~~not~~) observe this plugging.

DATE 3-12-85

INV. NO. 7306

3-5

Signed BOIC (TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KANSAS

BOIC