

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04920-00-00  
Spot: CNWSENE Sec/Twnshp/Rge: 21-20S-12W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HULME B Well Number: 6  
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

Conductor Pipe: Size feet: 8 1/2  
Surface Casing: Size 8.625 feet: 257  
Production: Size 5.5 feet: 3479  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/12/2002 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2440

Proposed Plugging Method: Emergency plug with rig over the hole.  
Junk in the hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/13/2002 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

09-11-2002 - Drilled out of the pipe at 630'. Decided to P&A.  
09-12-2002 - TIH with tubing to 620'.  
Mixed and pumped 225 sxs 60/40 pozmix - 10% gel with 500# hulls.  
POOH and shut in for 3 hours.  
TIH with tubing to 620'.  
Mixed and pumped 150 sxs common with 3% CaCl.  
POOH. SIFN.  
09-13-2002 - TIH with tubing to 150' and circulated cement with 25 common with 3% CaCl.  
Hooked onto 8 5/8" and pumped 25 sxs cement.  
S.I.P. 200#.

RECEIVED  
SEP 17 2002  
KCC WICHITA

Remarks: SERVICE ACID, LLC.

Plugged through: TBG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

INVOICED Form CP-2/3

DATE 9-18-02

INV. NO. 2003060519

SEP 16 2002

HONAKER-DAVIS

#6 HULME 'B'

21-20-12W 53  
NW SE NE

Contr. HONAKER-DAVIS

BARTON County

E. 18 1/4 RB Comm. 1-23-58 Comp. 3-28-58 IP 258 BOPD/PHY POT

Tops	Depth	Datum	Casing
ANH	650	1184	8" 257
TOP	2852	-1018	5" 3479
HEEB	3007	-1173	
BR LM	3126	-1292	DST 3160-90/1 HR, G/1 1/2", GA
KC	3143	-1309	1700 MCFG/5": 1040 MCFG/15"
			75' FR OIL, BHP 786#
			PERF 3422-28: 2 BOPH: ACID
			500
ERO ARB	3387	-1553	
ARB	3400	-1566	
			WORKMAN NW POOL
TD	3480	-1646	

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

