

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1962  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Adams Well No. # 1

Location C SW SW NE Sec. 21 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3588

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 5 PM Day 8 Month 12 Year 1962

The Above well, was plugged as follows:

8 5/8" 318' Cwc.

Sanded hole back to 3270' & dumped 4 sax cement with dump bailer.

Pulled pipe, to 450' & circulated hole with mud. Pulled pipe to 280'

& displaced 25 sax cement. Pulled remaining pipe; set rock bridge @

40' & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truesell  
Well Plugging Supervisor

DATE 12/12/62

INV. NO. 6209-u